

Date Received for Clearance Process (MMYY/DD)		INFORMATION CLEARANCE FORM	
<b>A. Information Category</b> <input type="checkbox"/> Abstract <input type="checkbox"/> Journal Article <input type="checkbox"/> Summary <input type="checkbox"/> Internet <input type="checkbox"/> Visual Aid <input type="checkbox"/> Software <input checked="" type="checkbox"/> Full Paper <input type="checkbox"/> Report <input type="checkbox"/> Other _____		<b>B. Document Number</b> <del>HNF-FP-24488</del> <b>HNF-24488-FP Rev.0</b>	
		<b>C. Title:</b> Management of Transuranic Waste Retrieval Project Risks - Successes in the Startup of the Hanford 200 Area TRU Waste Retrieval Project	
		<b>D. Internet Address</b>	
<b>E. Required Information</b>			
1. Is document potentially Classified? <input checked="" type="radio"/> No <input type="radio"/> Yes (MANDATORY) <i>Robert D. Greenwell</i> Manager's Signature Required  If Yes _____ <input type="radio"/> No <input type="radio"/> Yes Classified ADC Signature Required		3. Does Information Contain the Following: (MANDATORY) a. New or Novel (Patentable) Subject Matter? <input checked="" type="radio"/> No <input type="radio"/> Yes If "Yes", Disclosure No.: _____ b. Information Received in Confidence, Such as Proprietary and/or Inventions? <input checked="" type="radio"/> No <input type="radio"/> Yes If "Yes", Affix Appropriate Legends/Notices. c. Copyrights? <input checked="" type="radio"/> No <input type="radio"/> Yes If "Yes", Attach Permission. d. Trademarks? <input checked="" type="radio"/> No <input type="radio"/> Yes If "Yes", Identify in Document.	
2. References in the Information are Applied Technology <input checked="" type="radio"/> No <input type="radio"/> Yes Export Controlled Information <input checked="" type="radio"/> No <input type="radio"/> Yes		4. Is Information requiring submission to OSTI? <input checked="" type="radio"/> No <input type="radio"/> Yes 5. Release Level? <input checked="" type="radio"/> Public <input type="radio"/> Limited	
<b>F. Complete for a Journal Article</b>			
1. Title of Journal _____			
<b>G. Complete for a Presentation</b>			
1. Title for Conference or Meeting _____ 2. Group Sponsoring _____ 3. Date of Conference _____ 4. City/State _____ 5. Will Information be Published in Proceedings? <input type="radio"/> No <input type="radio"/> Yes 6. Will Material be Handed Out? <input type="radio"/> No <input type="radio"/> Yes			
<b>H. Author/Requestor</b> ROLAND D. GREENWELL <i>Robert D. Greenwell</i> (Print and Sign)		Responsible Manager DE McKenney (Print and Sign)	
<b>I. Reviewers</b>			
	Yes	Print	Signature
General Counsel	<input type="checkbox"/>	_____	<i>see attached Email</i>
Office of External Affairs	<input type="checkbox"/>	_____	_____
DOE-RL	<input type="checkbox"/>	_____	_____
Other	<input checked="" type="checkbox"/>	<i>M.A. Williams (21)</i>	<i>M.A. Williams</i>
Other	<input type="checkbox"/>	_____	_____
Public Y/N (if N, complete J)			
			Y / N
			Y / N
			Y / N
			<input checked="" type="radio"/> Y / N
			Y / N
<b>J. If Information Includes Sensitive Information and is not to be released to the Public indicate category below.</b>			
<input type="checkbox"/> Applied Technology <input type="checkbox"/> Protected CRADA <input type="checkbox"/> Personal/Private <input type="checkbox"/> Export Controlled <input type="checkbox"/> Proprietary <input type="checkbox"/> Procurement-Sensitive <input type="checkbox"/> Business-Sensitive <input type="checkbox"/> Patentable <input type="checkbox"/> Predecisional <input type="checkbox"/> Other (Specify) _____ <input type="checkbox"/> UCNI		Information Clearance Approval 	
<b>K. If Additional Comments, Please Attach Separate Sheet</b>			

**Fouad, Nancy A**

---

**From:** Greenwell, Doug  
**Sent:** Thursday, January 20, 2005 2:33 PM  
**To:** Fouad, Nancy A  
**Subject:** FW: Approval of WM 05 Paper

Nancy,

DOE approval.

Doug

-----Original Message-----

**From:** French, Mark S  
**Sent:** Thursday, January 20, 2005 11:35 AM  
**To:** Greenwell, Doug  
**Subject:** FW: Approval of WM 05 Paper

Looks OK to me. A few editorial comments but nothing serious. Gregg had one suggestion below, but it's up to you.

*Mark French  
Federal Project Director  
Solid/Liquid Waste Disposal  
373-9863*

---

**From:** Nishimoto, Gregg L  
**Sent:** Thursday, January 20, 2005 6:49 AM  
**To:** French, Mark S  
**Subject:** RE: Approval of WM 05 Paper

I think they should take more credit for use of the CRAL and its development, especially in the lessons learned section. The thoroughness of their pre-retrieval investigations has aided in avoiding problems as well as maintaining a high retrieval rate.

---

**From:** French, Mark S  
**Sent:** Wednesday, January 19, 2005 10:40 AM  
**To:** Nishimoto, Gregg L  
**Subject:** FW: Approval of WM 05 Paper  
**Importance:** High

Any comments?

1/20/2005

*Mark French*  
*Federal Project Director*  
*Solid/Liquid Waste Disposal*  
*373-9863*

---

**From:** Greenwell, Doug  
**Sent:** Tuesday, January 18, 2005 11:48 AM  
**To:** French, Mark S; McKenney, Dale E; Norris, Kenneth M (Ken); Dunn, Deborah J  
**Cc:** Brogdon, Aléda J; Aardal, Janis D; Jeppson, LaRae G  
**Subject:** Approval of WM 05 Paper  
**Importance:** High

Attached is a paper I am submitting to the WM'05 conference for your approval. The final deadline for paper submittals is this Friday so I request that you provide e-mail approval ASAP. I apologize in advance for the short notice, however, the conference failed to notify me that my abstract was approved. The session chair requested that I complete the paper because he believes the topic is important to the conference. I worked this weekend to get this paper together and I'm asking that you help me get it submitted on time.

Please contact me if you have any questions.

Doug Greenwell

**Fouad, Nancy A**

---

**From:** Greenwell, Doug  
**Sent:** Thursday, January 20, 2005 2:33 PM  
**To:** Fouad, Nancy A  
**Cc:** Jeppson, LaRae G  
**Subject:** FW: Approval of WM 05 Paper

Nancy,

Legal approval.

Doug

-----Original Message-----

**From:** Norris, Kenneth M (Ken)  
**Sent:** Tuesday, January 18, 2005 1:50 PM  
**To:** Greenwell, Doug  
**Subject:** RE: Approval of WM 05 Paper

Looks fine, Doug; use this e-mail as authorization to clear the document by the general counsel.

Ken Norris

---

**From:** Greenwell, Doug  
**Sent:** Tuesday, January 18, 2005 11:48 AM  
**To:** French, Mark S; McKenney, Dale E; Norris, Kenneth M (Ken); Dunn, Deborah J  
**Cc:** Brogdon, Aleda J; Aardal, Janis D; Jeppson, LaRae G  
**Subject:** Approval of WM 05 Paper  
**Importance:** High

Attached is a paper I am submitting to the WM'05 conference for your approval. The final deadline for paper submittals is this Friday so I request that you provide e-mail approval ASAP. I apologize in advance for the short notice, however, the conference failed to notify me that my abstract was approved. The session chair requested that I complete the paper because he believes the topic is important to the conference. I worked this weekend to get this paper together and I'm asking that you help me get it submitted on time.

Please contact me if you have any questions.

Doug Greenwell

**Fouad, Nancy A**

---

**From:** Greenwell, Doug  
**Sent:** Thursday, January 20, 2005 2:34 PM  
**To:** Fouad, Nancy A  
**Cc:** Jeppson, LaRae G  
**Subject:** FW: Approval of WM 05 Paper  
**Attachments:** 5134 Roland D Greenwell-DD.doc

Nancy,

Communications approval.

Doug

-----Original Message-----

**From:** Dunn, Deborah J  
**Sent:** Wednesday, January 19, 2005 7:50 AM  
**To:** Greenwell, Doug  
**Subject:** RE: Approval of WM 05 Paper

Dear Doug,

This paper have my approval for Public Release. I am attaching a version with my edits. You can use this e-mail message as verification for box I./Office of External Affairs approval on the Information Clearance Form.

Deborah Dunn  
Reviewer for Office of External Affairs

-----Original Message-----

**From:** Greenwell, Doug  
**Sent:** Tuesday, January 18, 2005 11:48 AM  
**To:** French, Mark S; McKenney, Dale E; Norris, Kenneth M (Ken); Dunn, Deborah J  
**Cc:** Brogdon, Aleda J; Aardal, Janis D; Jeppson, LaRae G  
**Subject:** Approval of WM 05 Paper  
**Importance:** High

Attached is a paper I am submitting to the WM'05 conference for your approval. The **final deadline** for paper submittals is this **Friday** so I request that you provide e-mail approval ASAP. I apologize in advance for the short notice, however, the conference failed to notify me that my abstract was approved. The session chair requested that I complete the paper because he believes the topic is important to the conference. I worked this weekend to get this paper together and I'm asking that you help me get it submitted on time.

Please contact me if you have any questions.

Doug Greenwell

1/20/2005

# Management of Transuranic Waste Retrieval Project Risks - Successes in the Startup of the Hanford 200 Area TRU Waste Retrieval Project

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the  
U.S. Department of Energy under Contract DE-AC06-96RL13200

**Fluor Hanford**

P.O. Box 1000  
Richland, Washington

Approved for Public Release;  
Further Dissemination Unlimited

# Management of Transuranic Waste Retrieval Project Risks - Successes in the Startup of the Hanford 200 Area TRU Waste Retrieval Project

R. D. Greenwell  
Fluor Hanford, Inc.

Date Published  
January 2005

To Be Presented at  
WASTE MANAGEMENT 2005

WASTE MANAGEMENT SYMPOSIUM  
TOUSON, ARIZONA

FEB 27, 2005 - MAR 03, 2005

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the  
U.S. Department of Energy under Contract DE-AC06-96RL13200

**Fluor Hanford**  
P.O. Box 1000  
Richland, Washington

**Copyright License**

By acceptance of this article, the publisher and/or recipient acknowledges the U.S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this paper.

  
Release Approval 1/20/05  
Date

**Approved for Public Release;  
Further Dissemination Unlimited**

**LEGAL DISCLAIMER**

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This document is available to the U.S. Department of Energy and its contractors, in paper from the Office of Scientific and Technical Information (OSTI). It is available for sale to the public from the national Technical Information Service (NTIS).

This report has been reproduced from the best available copy. Available in paper copy.

## **MANAGEMENT OF TRANSURANIC WASTE RETRIEVAL PROJECT RISKS – SUCCESSSES IN THE STARTUP OF THE HANFORD 200 AREA WASTE RETRIEVAL PROJECT**

**R.D. Greenwell, Duratek Federal Services of Hanford**

### **ABSTRACT**

A risk identification and mitigation method applied to the Transuranic (TRU) Waste Retrieval Project performed at the Hanford 200 Area burial grounds is described. Retrieval operations are analyzed using process flow diagramming, and the anticipated project contingencies are included in the Authorization Basis and operational plans. Examples of uncertainties assessed include degraded container integrity, bulged drums, unknown containers, and releases to the environment. Identification and mitigation of project risks contributed to the safe retrieval of over 1700 cubic meters of waste without significant work stoppage and below the targeted cost per cubic meter retrieved. This paper will be of interest to managers, project engineers, regulators, and others who are responsible for successful performance of waste retrieval and other projects with high safety and performance risks.

### **INTRODUCTION**

Successes in the retrieval of TRU wastes from the Hanford 200 Area burial grounds resulted from thorough project risk identification and the full integration of mitigation strategies into daily operations. From November, 2003 to January, 2005, 7,524 containers (1,700 cubic meters) of waste were retrieved. Of this population, 625 heavily corroded, breached, damaged, and bulged containers required the application of predetermined risk response actions that were completed with no significant safety incidents or work interruptions.

### **PROJECT BACKGROUND**

Over 15,000 cubic meters of suspect-TRU waste was retrievably stored in earth-covered trenches at the Hanford 200 Area burial grounds from 1970 to 1988 (1). Suspect-TRU waste was defined as a separate waste category by the U.S. Atomic Energy Commission (AEC) in 1970 and was separated from low-level waste (LLW) and retrievably stored. In 1973, the AEC changed the definition of TRU waste to waste containing greater than 10nCi/gm (nanocuries/gram) of TRU radionuclides. The definition of TRU was changed again in 1984 to specify only waste containing greater than 100 nCi/gm of TRU radionuclides; therefore, some of the suspect TRU waste initially placed in storage would now be defined as LLW. -After 1988, TRU waste was stored in the Central Waste Complex (CWC), a Resource Conservation and Recovery Act (RCRA) permitted storage unit.

The majority of the Retrievably sStored wWaste (RSW), consisting of approximately 26,200 drums, areis placed on asphalt floored trenches in 3 to 4 high vertical stacks layered with plywood. Additionally, boxes of various size and construction and other miscellaneous containers are intermingled with the drums. Storage configurations varied including horizontal and diagonal arrays, and random dumping. A plastic tarp material was placed over the stacks during the later years of retrievable storage and 1 to 3 meters of soil cover was typically placed over each trench. Vertical plastic pipe "vent risers" were placed, extending from the asphalt pad through the earthen cover in some trenches. The vent risers were intended to reduce moisture content in RSW stacks; however, they were later determined to be ineffective. The RSW trenches are located in four separate burial grounds of the 200 aArea.

A pilot retrieval project was performed in 1994 to investigate container integrity and provide planning information for future full-scale retrieval operations. In-situ inspections were performed on tarp-covered 208 liter (55 gallon) RSW drums to evaluate drum corrosion degradation. The pilot project concluded that drum corrosion was less than expected, affecting only a small percentage of drums. Corroded drums were predominately those on the outer edges of the stack and in contact with the tarp material or soil. Breached containers causing contamination were encountered. The maximum drum wall corrosion rate was estimated to be 2 mils/year.

Retrieval of uncovered RSW drums began in 1996. An earthen-cover was never completed over several stacks of drums at the end of retrievable storage operations in 1988. About 1,100 drums were retrieved from 1996-2001, removing the uncovered RSW containers. Further retrieval required completion of a revised Authorization Basis for the earthen-covered portions of the trenches. Vadose zone and near-surface soil vapor sampling for volatile organic compounds (VOCs) wcreas conducted in the 218-W-4C burial ground and adjacent areas during August and September, 2002. This investigation was conducted under a Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) remedial investigation of VOC releases in the general area. Carbon tetrachloride was detected at all but one of 27 vent risers sampled. A distinct "hot spot" with a maximum concentration of 1,760 ppmv was detected at the east end of Trench 4 (2). The discovery of VOCs in the trenches raised stakeholder concerns about releases from RSW and ultimately became an impetuous to revise the enforceable milestones for TRU waste retrieval established in the Hanford Tri-Party Agreement. The new regulatory agreement, finalized in the fall of 2003, directed the order in which trenches will be retrieved, included near-term project start-up milestones, and created new retrieval production milestones that accelerate yearly, i.e., 1200 cubic meters in 2004, 1500 cubic meters in 2005, etc. (3).

The 33-year history of waste storage preceding full-scale retrieval created significant uncertainties in the waste configuration and site conditions. These uncertainties, combined with safety and regulatory requirement challenges, created high risks that needed to be managed to assure project success.

## RISK IDENTIFICATION AND STRATEGY DEVELOPMENT

Retrieval project planning began with a review of similar TRU waste retrieval projects performed across the DOE complex. Occurrence reports were reviewed including those of past operational experiences within the Hanford burial grounds (4,5,6). Project personnel from Savannah River Site, Idaho National Environmental Engineering Laboratory, Los Alamos National Laboratory, Rocky Flats, and Oak Ridge National Laboratory were contacted. Good practices and retrieval techniques were identified. Hazards discussed include chemical/radiological contamination, industrial safety, and site-specific conditions such as burial ground subsidence. A significant concern across the DOE complex is the presence of hydrogen and VOCs in un-vented TRU waste drums due to radiolysis and chemical corrosion of drum and waste contents. Concentrations of hydrogen above the lower flammability limit have been observed in retrieved waste drums at several DOE sites, posing the threat of fire or deflagration. Venting of suspect- TRU drums was not commonly performed prior to 1978 at the Hanford sSite, and therefore, an estimated 8,190 drums are stored in the RSW trenches without venting devices. An evaluation was conducted of the DOE complex-wide experience with hydrogen generation, accumulation, diffusion, and leakage from retrieved TRU waste containers (7). The study identified over 42,000 drums retrieved across the complex. Hydrogen data were available from venting operations of 23,677 drums. Greater than 15 % by volume (vol.%) hydrogen was found in 4 percent of un-vented drums. A deflagration event with hydrogen greater than 15 vol.% is expected to cause energetic drum lid loose and partial ejection of drum contents. One objective of the study was to identify parameters such as radionuclide content or waste form that could be used to predict hydrogen generation without reliance on conservative modeling codes such as RADCALC (8). The hope of the project team was that judgments about the potential for hydrogen gas buildup in drums could be made, based on a review of storage records. However, no reliable correlations could be made through review of existing data. Differences in the distribution of radionuclides within a container, waste packaging methods, and other variables complicate attempts to predict hydrogen levels and support the need to vent all TRU waste containers using appropriate handling and venting methods to protect workers.

Input from related DOE projects formed the basis for the Hanford TRU waste retrieval strategy; however, no project performed to date could be identified with analogous uncertainties, safety, regulatory, and performance requirements. Controlling project risks became the overarching consideration during retrieval planning. Key features of the retrieval strategy selected include: continuous year-round operations, mobile equipment and support facilities, outdoor retrieval (no enclosure structure), multiple retrieval sites operated simultaneously, dig-face radiological/chemical monitoring, and field sorting of waste streams prior to transportation to treatment, storage, and disposal (TSD) facilities to prepare for final disposition.

## PROCESS FLOW DIAGRAMMING AND RISK ANALYSIS

The retrieval Project Execution Plan documented a rigorous approach to monitor and control risks (9). Storage records exist for much of the RSW providing information on waste generators, radionuclide inventories, and to a lesser degree, chemical inventories. However, the completeness and reliability of records greatly diminishes with age, creating uncertainty in work definition and hazards analysis for older trenches. Many containers were expected to be degraded due to the number of years stored underground. A number of variable steps are involved with the retrieval process to account for the issues involved with degraded containers. It was recognized early in project planning that a detailed process flow examination was needed to assure integration of Authorization Basis documents, selection and sizing of unit operations, and identification of contingencies. A basic process description was developed from planning inputs (10). The normal process steps for retrieval operations consist of: 1) trench module records analysis and retrieval safety evaluation, 2) vapor vacuum extraction operations in trenches with elevated VOCs, 3) exploratory and final trench excavations, 4) removal of containers from the uncovered stack, 5) initial container inspection and staging, 6) waste designation including nondestructive assay to sort TRU from non-TRU waste, 7) venting of TRU drums without venting devices, and 8) transportation to treatment, storage, and disposal (TSD) facilities for further processing and disposition. TRU waste containers are characterized at Hanford TSD facilities, repackaged if necessary, and certified for shipment to the Waste Isolation Pilot Plant. MLLW and LLW are processed for compliant disposal at Hanford. Development of the process description and flow diagram provided the detailed information needed to complete the Preliminary Hazards Assessment, National Environmental Policy Act evaluation, air permit, operational procedures, and final selection of equipment and materials. Contingency process flow paths were also fully developed for all anticipated abnormal retrieval conditions including heavily corroded, breached, damaged, bulged, and unknown containers, as well as environmental releases, classified wastes, and unexpected emergent conditions (Figure 1).






Figure 2. Trench Excavation and Drum Exhumation Operations at 218-W-4C, Trench 4.

Workers are involved in the selection of equipment and development of procedures for all process flow paths improving performance, reliability of operations, and feedback from work teams. A mockup RSW trench constructed outside of the nuclear facility proved invaluable for testing equipment, demonstration of processes, and training work teams on retrieval procedures. Vapor vacuum extraction systems installed on vent risers of burial ground 218-W-4C, Trench 4 effectively reduced ambient VOC levels to below action levels before retrieval operations commenced. The readiness assessment and startup plan for the project were completed with minimal corrective actions due to the effectiveness of integration and work team training. Monitoring of initial field operations confirmed that the retrieval strategy was valid and that trench configurations and RSW container integrity were successfully predicted through the planning process, resulting in no significant work stoppages.

The most frequently encountered abnormal condition is excessively corroded drums. The distribution of abnormal containers so far is 80% corrosion, 17% damaged, and 3% other (includes contamination, high dose, liquids, unknowns, and bulging). Extensive corrosion in some trench locations have resulted in breached drums and contamination levels within the stack to 7,000 dpm/100cm<sup>2</sup> alpha, and 80,000 dpm/100 cm<sup>2</sup> beta-gamma. No releases to the environment have been identified. Hydrogen monitoring results within newly vented TRU waste drums are summarized in Table 1. Gas chromatograph results confirmed the presence of significant hydrogen levels in a small percentage of the TRU waste drum population consistent with DOE complex experience. Following venting, drums with elevated hydrogen levels are retained in a protected zone until vent filter diffusion time is completed. Waste designations following initial processing approximate

55 percent TRU waste, 40 percent mixed low-level waste (MLLW), and 5 percent low level waste (LLW).

Table 1. Hydrogen Concentrations at Venting of 2,052 Drums Retrieved From the 218-W-4C Burial Ground

	Percent by Volume Hydrogen in Drum Headspace <sup>a</sup>				
	<1%	1-4%	5-15%	16-30%	31-50% <sup>b</sup>
Un-Vented TRU Drums	1427	415	171	34	5
Percent of Population	69.6	20.2	8.3	1.7	0.2

<sup>a</sup> Hydrogen is flammable in concentrations of 4.1 to 74.2 vol.% in air

<sup>b</sup> 50% is the maximum concentration observed

The project manager uses process flow diagrams to optimize unit operation throughput. Drum counts at stages along the process flow are monitored and adjustments in work assignments and drum queuing are made to maximize productivity. Responses to changing weather and site hazards are also made as necessary. This analysis is also helpful to identify and prioritize investments to achieve innovations and continuous improvements.

## LESSONS LEARNED

The following is a summary of lessons learned from the planning and implementation of TRU waste retrieval at Hanford.

1. Communications across the DOE complex by teams performing similar high-risk projects provide valuable input throughout the life of the job (12).
2. A pilot retrieval or similar site investigation provides vital information to the project plan about site conditions and hazards identification.
3. The risk response strategy is critical to the success of the project. The strategy should be utilized to guide development of the project execution plan.
4. A detailed process description should be developed early in the planning phase. Process flow diagramming or other appropriate tools can be used to identify contingencies that must be fully developed into the operational plan.
5. Design the operational plan for continuous throughput whenever possible to maximize efficiency. Avoid the stops and starts of batch-type operations.
6. Mockup facilities are invaluable for demonstrating equipment, processes, and training work teams.

7. Worker involvement should begin during the planning phase to obtain important feedback and ownership of the approach.
8. Maintain multiple retrieval faces whenever possible to provide flexibility in drum feed sources and the ability to shift operations as necessary to respond to abnormal conditions.
9. Monitor risk responses continuously to identify changing assumptions and to identify opportunities to improve the effectiveness of responses.
10. A potential disadvantage of this approach is that time and resources must be applied to the planning process to implement all analyzed flow paths. Unknown conditions will still be encountered and the project plan must provide for response to unknowns.

## CONCLUSION

Process flow analysis has proven to be an effective method to identify and mitigate risks at the Hanford TRU waste retrieval project. Successful application of this approach requires full integration of risk responses into the operational plan. Equally important is the need to involve workers in the risk response process and provide them with the authority to select responses and apply process improvements. Project leaders and stakeholders must factor in realistic expectations about the planning investment necessary to achieve successful high-risk projects. Risk analysis must also be applied beyond the planning phase throughout the life of the project.

## REFERENCES

- [1] J.D. Anderson, "The History of the 200 Area Burial Ground Facilities", WHC-EP 0912, Westinghouse Hanford Company, (1996).
- [2] V.J. Rohay, D.C. Weekes, "200-PW-1 Operable Unit Report on Step I Sampling and Analysis of Dispersed Carbon Tetrachloride Vadose Zone Plume", Fluor Hanford, (2003).
- [3] *Hanford Federal Facility Agreement and Consent Order*, 89-10, Rev. 6, April 2003, as amended by Change Package M-91-03-01, "Modification of Hanford Facility Agreement and Consent Order M-91 Series Provisions".
- [4] D.L. McMurtrey, "Two Unvented Transuranic Waste Drums in Trench 1 Exceed the Gram Limits Approved in a Justification for Continued Operations (USQ)" RL-PHMC-SOLIDWASTE-2001-0004, Fluor Hanford, (2001).
- [5] E.M. Poole, "Wheel of Fork Truck Dropped Into Undetected Burial Ground Subsidence", RL-PHMC-SOLIDWASTE-2003-0004, Fluor Hanford, (2003).
- [6] J.C. Hickey, "Fire in a Bulged Drum Results in an Emergency 'Alert' Condition", ID-BNFL-AMWTF-2003-0008, BNFL, Inc., (2003).
- [7] L. Dayley, "Analysis of Available Hydrogen Data and Accumulation of Hydrogen in Unvented TRU Drums", HNF-9411, Fluor Hanford, (2001).

- [8] J.G. McFadden, et. al., ENG-RPT-034, Rev. 0, "RADCALC for Windows Version 2.11, Volume II: Technical Manual, Waste Management Technical Services, (1999).
- [9] M.A. Cahill, "Transuranic Waste Retrieval Project Execution Plan", HNF-9432, Fluor Hanford, (2003).
- [10] L. Dayley, "Process Description for the Retrieval of Earth-Covered Transuranic Waste Containers at the Hanford Site", HNF-5597, Fluor Hanford, (2003).
- [11] J.R. Weidert, "Technical Safety Requirements (TSR) For the Solid Waste Operations Complex (SWOC)", HNF-15280, Fluor Hanford, (2004).
- [12] M.A. Cahill, "Transuranic (TRU) Waste Retrieval Safety Workshop Summary Report", HNF-23630, Fluor Hanford, (2005).