


PPPL-4068

PPPL-4068

## Recent Liquid Lithium Limiter Experiments in CDX-U

R. Majeski, S. Jardin, R. Kaita, T. Gray, P. Marfuta, J. Spaleta,  
J. Timberlake, L. Zakharov, G. Antar, R. Doerner, S. Luckhardt,  
R. Seraydarian, V. Soukhanovskii, R. Maingi, M. Finkenthal,  
D. Stutman, D. Rodgers, and S. Angelini

May 2005



Prepared for the U.S. Department of Energy under Contract DE-AC02-76CH03073.

# **PPPL Report Disclaimers**

## **Full Legal Disclaimer**

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

## **Trademark Disclaimer**

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

# **PPPL Report Availability**

This report is posted on the U.S. Department of Energy's Princeton Plasma Physics Laboratory Publications and Reports web site in Fiscal Year 2005. The home page for PPPL Reports and Publications is: [http://www.pppl.gov/pub\\_report/](http://www.pppl.gov/pub_report/)

## **Office of Scientific and Technical Information (OSTI):**

Available electronically at: <http://www.osti.gov/bridge>.

Available for a processing fee to U.S. Department of Energy and its contractors, in paper from:

U.S. Department of Energy  
Office of Scientific and Technical Information  
P.O. Box 62  
Oak Ridge, TN 37831-0062  
  
Telephone: (865) 576-8401  
Fax: (865) 576-5728  
E-mail: [reports@adonis.osti.gov](mailto:reports@adonis.osti.gov)

## **National Technical Information Service (NTIS):**

This report is available for sale to the general public from:

U.S. Department of Commerce  
National Technical Information Service  
5285 Port Royal Road  
Springfield, VA 22161  
  
Telephone: (800) 553-6847  
Fax: (703) 605-6900  
Email: [orders@ntis.fedworld.gov](mailto:orders@ntis.fedworld.gov)  
Online ordering: <http://www.ntis.gov/ordering.htm>

## Recent liquid lithium limiter experiments in CDX-U

R. Majeski 1), S. Jardin 1), R. Kaita 1), T. Gray 1), P. Marfuta 1), J. Spaleta 1), J. Timberlake 1), L. Zakharov 1), G. Antar 2), R. Doerner 2), S. Luckhardt 2), R. Seraydarian 2), V. Soukhanovskii 3), R. Maingi 4), M. Finkenthal 5), D. Stutman 5), D. Rodgers 6), S. Angelini 7)

1) Princeton Plasma Physics Laboratory, Princeton, NJ USA

2) University of California at San Diego, San Diego, CA USA

3) Lawrence Livermore National Laboratory, Livermore, CA USA

4) Oak Ridge National Laboratory, Oak Ridge, TN USA

5) Johns Hopkins University, Baltimore, MD USA

6) University of Delaware, Wilmington, DE USA

7) Columbia University, New York, NY USA

**Abstract.** Recent experiments in the Current Drive eXperiment – Upgrade (CDX-U) provide a first-ever test of large area liquid lithium surfaces as a tokamak first wall, to gain engineering experience with a liquid metal first wall, and to investigate whether very low recycling plasma regimes can be accessed with lithium walls. The CDX-U is a compact ( $R=34$  cm,  $a=22$  cm,  $B_{\text{toroidal}} = 2$  kG,  $I_p = 100$  kA,  $T_e(0) \sim 100$  eV,  $n_e(0) \sim 5 \times 10^{19} \text{ m}^{-3}$ ) spherical torus at the Princeton Plasma Physics Laboratory. A toroidal liquid lithium pool limiter with an area of  $2000 \text{ cm}^2$  (half the total plasma limiting surface) has been installed in CDX-U. Tokamak discharges which used the liquid lithium pool limiter required a fourfold lower loop voltage to sustain the plasma current, and a factor of 5-8 increase in gas fueling to achieve a comparable density, indicating that recycling is strongly reduced. Modeling of the discharges demonstrated that the lithium limited discharges are consistent with  $Z_{\text{effective}} < 1.2$  (compared to 2.4 for the pre-lithium discharges), a broadened current channel, and a 25% increase in the core electron temperature. Spectroscopic measurements indicate that edge oxygen and carbon radiation are strongly reduced.

e-mail contact of main author: rmajeski@pppl.gov

PACS: 52.55.Fa, 52.40.Hf

## 1. Introduction

Liquid lithium walls have been identified as a potential solution to many of the engineering problems associated with the first wall of a fusion reactor [1]. In addition, a nonrecycling liquid lithium boundary is predicted to allow access to fundamentally different tokamak equilibria [2]. Experiments in the Current Drive eXperiment – Upgrade (CDX-U) have provided valuable insight on the practical engineering aspects of handling and stabilizing liquid lithium in a tokamak environment, as well as a confirmation that liquid lithium walls do indeed produce fundamental changes in a tokamak discharge.

The benefits of a surface that has low or no recycling conditions have been demonstrated during the “Deposition of Lithium by Laser Outside of Plasma” (DOLLOP) lithium wall conditioning experiments,[3] for example, in the Tokamak Fusion Test Reactor (TFTR). Since TFTR had carbon walls, intercalation of the lithium into the graphite is a complicating factor in those experiments. Lithium limiter experiments have also been performed on the T-11M device,[4] where a capillary porous rail limiter system was used to form a “self-restoring” liquid lithium surface.[5] The T11-M limiter is relatively small, and evaporated lithium wall coatings are thought to be a factor in the experiments.[4] In this paper, we focus on experiments in which a substantial fraction of the plasma-facing surface is liquid lithium.

CDX-U is a small spherical torus, with a major radius  $R_0=34$  cm, minor radius  $a=22$  cm, aspect ratio = 1.5, elongation  $\kappa = 1.6$ , toroidal field  $B_T = 2.1$  kG, and ohmic current  $I_p \leq 90$  kA. With the exception of the capacitor banks for the OH system and the field null formation coils, the power supplies are preprogrammed and controlled by digital to analog waveform generators. At present, there is no feedback control on the plasma current; therefore, the applied loop voltage magnitude and time history is approximately the same for every discharge. For this reason, the plasma current achieved is a good measure of plasma performance in CDX-U. Deuterium was the working gas for all experiments.

The first experiments with lithium limiters in CDX-U employed a small area rail limiter.[6] Following the rail limiter experiments, a shallow, heated, stainless steel tray was installed at the bottom of the CDX-U vacuum vessel. The tray has an inner radius of 24 cm, is 10 cm

wide and 0.5 cm deep, and exposes 2000 cm<sup>2</sup> of lithium pool to the plasma. It is constructed in two halves, with a single electrical break to prevent induction of large currents in the tray due to the ohmic transformer. The tray ends on either side of the electrical break are connected to vacuum electrical feedthroughs. One end of the tray is then externally connected to ground through a current transformer. The other end is not connected, which eliminates inductively driven tray currents due to ohmic transformer action. Currents drawn by the tray from the plasma either as a result of normal operations (limiter currents) or due to a disruption are therefore forced to run in the toroidal direction, parallel to the toroidal magnetic field. This construction is designed to eliminate the largest component of possible  $\mathbf{J} \times \mathbf{B}$  forces on the liquid lithium. A photograph of the tray installed in CDX-U is shown in Figure 1.

For the first experiments with the tray limiter, it was loaded under vacuum or dry argon with approximately 200 cm<sup>3</sup> of solid lithium in the form of rods, which were subsequently melted. This approach produced a partial (~50% coverage), uneven layer of lithium in the tray. Oxide and hydroxide surface coatings on the lithium were visually evident, and were only partially removed by glow discharge cleaning. Nevertheless, global improvements in impurity content and plasma performance were observed.[7]

For the experiments described here, a new fill system was developed by the University of California at San Diego PISCES group. This system injects liquid lithium onto the preheated (500° C) tray, under an atmosphere of argon, in order to obtain a uniform fill of the tray. Prior to the lithium fill, tokamak discharges were run for several months, using the empty stainless steel tray as a limiter. Afterwards, when sufficient baseline data had been obtained with a high recycling limiter, the tray was filled with approximately 500 cm<sup>3</sup> of liquid lithium. Subsequent cycles of reheating the tray, combined with 4-8 hour cycles of argon glow discharge cleaning, produced 100% coverage of the tray. In this case, argon glow discharge cleaning at tray temperatures of 300° C was effective at removing coatings of oxides and hydroxides which accumulate on the surface of the lithium at the normal base pressure of CDX-U ( $1 - 2 \times 10^{-7}$  Torr) during periods when the tokamak is not operating, producing a highly reflective metallic surface. Typically a “lithium pool” discharge denotes one in which the tray temperature is maintained at 300 °C or above, well above the melting point of lithium (186 °C). It should also be noted that at normal operating temperatures the evaporation rate of

the lithium is significant; this leads to lithium coatings on the windows (which is undesirable), as well as on the titanium carbide-coated, stainless steel, centerstack, which is a primary plasma limiter.

## 2. Plasma characteristics during lithium operations

A comparison of pre- and post- lithium discharges in deuterium is shown in Figure 2. The most obvious differences in the two discharges are in the fueling requirements and the loop voltage evolution. In the case of the discharge operated against the liquid lithium, a factor of 5 or more increase in the fueling is required. This corresponds to the maximum flow rate of the piezoelectric valve used to fuel CDX-U, and is still not sufficient to attain a plasma density comparable to the pre-lithium discharge. In the pre-lithium discharge, only a prefill is required to fuel the entire discharge. Recycling alone is sufficient to build and maintain density during the discharge. The density of the post- lithium discharges also pumps out promptly when gas puffing is terminated at 0.222 sec, with an e-folding time of 1 msec, which is approximately the energy confinement time for a CDX-U discharge. A quantitative determination of the global recycling coefficient is not available, since the fueling efficiency and particle confinement time are not known experimentally for these discharges. However, the observed particle pumpout is strongly suggestive of a very low recycling coefficient. Since the lithium tray limiter itself represents less than 50% of the total surface area wetted by the plasma, this result suggests that evaporation of the lithium in the tray and continual coating of the centerstack surface with fresh lithium may play a significant role in the discharge modifications seen with lithium.

Figure 3 is a summary plot of the fueling requirements, plotted as a function of the peak discharge plasma current, for pre- and post- lithium discharges in CDX-U. Note that although fueling of the lithium shots utilized the full gas throughput of the available valve (up to 60 Torr-liters  $\text{sec}^{-1}$ ) the maximum attainable density during lithium operations was approximately 75% of the pre-lithium discharges, which utilized only a deuterium prefill.

The differences in fueling are expected from previous experiments which indicate that liquid lithium has very low recycling properties. [8] Another indication of very low recycling in the post-lithium discharges is the reduction in  $D_\alpha$  emission from spectroscopy viewing the

centerstack, which is a primary limiting surface for the discharge. A comparison of pre- and post- lithium  $D_\alpha$  emission is shown in Figure 4.

The loop voltage evolution is also strikingly different for pre- and post- lithium discharges. Far lower loop voltages are required to maintain plasma current for the post- lithium discharges. Plasma termination does not occur until well after the loop voltage reverses. Whereas in a pre- lithium discharge, 2 V is insufficient to sustain the plasma current, 0.5 – 0.8V is sufficient to maintain the plasma current in a post- lithium discharge. During lithium operations it was determined that current ramps of 4 MA/sec could be sustained with less than 1.5 V loop voltage. This represents exceptionally low resistive flux consumption for a small tokamak. A comparison of pre- and post- lithium discharge loop voltage and plasma current behavior is shown in Figure 5.

Impurities, especially oxygen, are reduced during lithium operations. Data taken with a residual gas analyzer indicate that water levels in the chamber drop by an order of magnitude during operations with the liquid lithium limiter. The resultant reduction in plasma oxygen radiation is shown in Figure 6.

A direct measure of the core electron temperature was not available. However, a spectroscopic measurement of the Doppler broadened C IV line width indicates that the impurity ion temperature increases by over a factor of two for the lithium discharges. Spectroscopic measurements of the C IV line width for pre- and post- lithium discharges are shown in Figure 7. Note also that the carbon line intensity drops by an approximate factor of six for the lithium discharges; the carbon impurity content of the discharge is also significantly reduced during lithium operation.

The liquid lithium contained in the toroidal tray was also observed to be mechanically stable during tokamak discharges. Significant currents – up to 500A for 100  $\mu$ sec, or 100A for 10 msec – were drawn to the liquid lithium from the plasma as a result of vertical displacements or disruptions. The resultant current densities in the liquid lithium were in excess of 100 A-cm<sup>-2</sup>. However, there was no visual evidence of any lithium ejected from the tray after hundreds of discharges. Furthermore, fast (1,000 frame sec<sup>-1</sup>) camera imaging of the liquid

lithium surface detected no motion of the liquid surface during plasma operations. The stability of the lithium is likely due to the design of the tray, which forces all current conducted to ground to flow in the toroidal direction, parallel to the toroidal magnetic field, avoiding  $\mathbf{J} \times \mathbf{B}$  forces on the lithium. Therefore, no splashing of lithium out of the tray occurred during plasma operations. The tray design, which represents a toroidal bottom limiter geometry, presents advantages compared to poloidal limiter concepts proposed, for example, for Tore Supra.[9] The design approach taken in CDX-U appears to have successfully inhibited undesirable displacement of the liquid lithium during plasma operations.

### **3. Modeling with the Tokamak Simulation Code.**

The evolution of the loop voltage and current for pre- and post- lithium discharges with similar plasma current and density has been modeled with the Tokamak Simulation Code (TSC). Although the core electron temperature is not measured with Thomson scattering, soft x-ray measurements indicates that the peak electron temperature does not exceed approximately 150 eV for the lithium discharges; this is used as a constraint in the modeling. TSC indicates that the modeled internal inductance drops from 1.4 for the pre- lithium discharges to 0.65 for the post- lithium discharges. This drop in internal inductance is indicative of a significantly broadened current channel, in keeping with the analytic predictions for a very low recycling discharge.[2] Modeling also indicates that  $Z_{\text{effective}}$  drops by a factor of two (from 2.4 to 1.16) for lithium operation, which is in qualitative agreement with the observed reduction in impurity radiation. Within the above-mentioned constraint on the electron temperature, TSC modeling also suggests that a modest increase in peak electron temperature, from 120 to 150 eV, occurs for the lithium discharges.

### **4. Summary and conclusions**

The CDX-U experiments with a significant large area liquid lithium limiter have clearly demonstrated improvements, compared to former discharge results, in virtually every available measure of tokamak performance. The reduction in plasma resistivity as evidenced by the loop voltage characteristics is particularly remarkable for a small, ohmically driven tokamak. These improvements far exceed previously observed changes in CDX-U discharges



which employed either boronization or titanium gettering. Note that neither of these surface conditioning techniques were utilized for any of the discharges described here. The effects of liquid lithium plasma-facing components will be further explored in the Lithium Tokamak eXperiment (LTX), which is presently under construction at the Princeton Plasma Physics Laboratory.

## **5. Acknowledgements**

We acknowledge the efforts of L. Chousal and T. Lynch of the University of California at San Diego and especially J. Taylor of the Princeton Plasma Physics Laboratory. This work was supported by USDOE Contract No. DE-AC02-76-CHO3073.

## References

- [1] ABDOU, M. A., et al., “On the exploration of innovative concepts for fusion chamber technology”, *Fus. Eng. Des.* **54** (2001) 181.
- [2] ZAKHAROV, L. E., et al., “Ignited spherical tokamaks and plasma regimes with Li walls”, *Fus. Eng. Des.* **72** (2004) 149.
- [3] MANSFIELD, D. K., et al., “Enhancement of Tokamak Fusion Test Reactor performance by lithium conditioning”, *Phys. Plasmas* **3** (1996) 1892.
- [4] MIRNOV, S. V., et al., “Li – CPS limiter in tokamak T-11M”, *Fus. Eng. Des.* **65** (2003) 455.
- [5] ANTONOV, N. V., et al., “Experimental and calculated basis of the lithium capillary system as divertor material”, *J. Nucl. Mater.* **241-243** (1997) 1190.
- [6] ANTAR, G. Y., et al., “Plasma – lithium interaction in the CDX-U spherical torus”, *Fus. Eng. Des.* **60** (2002) 157.
- [7] MAJESKI, R., et al., “CDX-U operation with a large area liquid lithium limiter”, *J. Nucl. Mater.* **313-316** (2003) 625.
- [8] BALDWIN, M. J., et al., “Plasma interaction with lithium: Measurements of retention and erosion”, *Fus. Eng. Des.* **61-62** (2002) 231.
- [9] MARTIN, G., and LIPA, M., “Li3 first step studies of a liquid lithium limiter”, *Fus. Eng. Des.* **61-62** (2002) 237.

### Figure Captions

Figure 1. Interior of CDX-U showing the toroidal bottom tray limiter. Not visible are the heating elements, mounted on the bottom of the tray. The semicircular cutout in the tray at lower left permits interferometer access to central chords. Also visible are the heat shields installed to protect the lower vacuum vessel and centerstack, electrical connections to the heaters and tray halves (right), and tray thermocouples.

Figure 2. Comparison of plasma current, loop voltage, density, and fueling for a discharge limited by the toroidal stainless steel tray limiter, prior to filling with lithium, and for a discharge limited by liquid lithium. Note the large reduction in loop voltage required to sustain the plasma current, and the much higher fueling rates required for the liquid lithium limiter plasmas.

Figure 3. Summary plot of particle fueling for discharges utilizing the bare stainless steel tray as a limiter (squares), and for discharges limited by liquid lithium (triangles).

Figure 4. Comparison of edge  $D_\alpha$  emission for pre- lithium (squares) and post- lithium (triangles) discharges. The baseline evident in the lithium discharges is very consistent, and may be background  $D_\alpha$  emission due to gas puffing.

Figure 5. Loop voltage (a) and plasma current (b) comparison for pre- and post- lithium discharges. Note the zero in the loop voltage plot.

Figure 6. Oxygen II emission at the centerstack for plasmas limited by the stainless steel tray (squares) and by liquid lithium (triangles).

Figure 7. C IV line width measurements for (a) a pre- lithium discharge and (b), a post- lithium discharge. Peak plasma current for both discharges was 58 kA; the density of the lithium discharge was somewhat lower due to fueling limitations




Figure 1




Figure 2




Figure 3




Figure 4




Figure 5






Figure 6




Figure 7

## External Distribution

Plasma Research Laboratory, Australian National University, Australia  
Professor I.R. Jones, Flinders University, Australia  
Professor João Canalle, Instituto de Fisica DEQ/IF - UERJ, Brazil  
Mr. Gerson O. Ludwig, Instituto Nacional de Pesquisas, Brazil  
Dr. P.H. Sakanaka, Instituto Fisica, Brazil  
The Librarian, Culham Science Center, England  
Mrs. S.A. Hutchinson, JET Library, England  
Professor M.N. Bussac, Ecole Polytechnique, France  
Librarian, Max-Planck-Institut für Plasmaphysik, Germany  
Jolan Moldvai, Reports Library, Hungarian Academy of Sciences, Central Research Institute  
for Physics, Hungary  
Dr. P. Kaw, Institute for Plasma Research, India  
Ms. P.J. Pathak, Librarian, Institute for Plasma Research, India  
Dr. Pandji Triadyaksa, Fakultas MIPA Universitas Diponegoro, Indonesia  
Professor Sami Cuperman, Plasma Physics Group, Tel Aviv University, Israel  
Ms. Clelia De Palo, Associazione EURATOM-ENEA, Italy  
Dr. G. Grosso, Istituto di Fisica del Plasma, Italy  
Librarian, Naka Fusion Research Establishment, JAERI, Japan  
Library, Laboratory for Complex Energy Processes, Institute for Advanced Study,  
Kyoto University, Japan  
Research Information Center, National Institute for Fusion Science, Japan  
Dr. O. Mitarai, Kyushu Tokai University, Japan  
Dr. Jiangang Li, Institute of Plasma Physics, Chinese Academy of Sciences,  
People's Republic of China  
Professor Yuping Huo, School of Physical Science and Technology, People's Republic of China  
Library, Academia Sinica, Institute of Plasma Physics, People's Republic of China  
Librarian, Institute of Physics, Chinese Academy of Sciences, People's Republic of China  
Dr. S. Mirnov, TRINITI, Troitsk, Russian Federation, Russia  
Dr. V.S. Strelkov, Kurchatov Institute, Russian Federation, Russia  
Professor Peter Lukac, Katedra Fyziky Plazmy MFF UK, Mlynska dolina F-2,  
Komenskeho Univerzita, SK-842 15 Bratislava, Slovakia  
Dr. G.S. Lee, Korea Basic Science Institute, South Korea  
Dr. Rasulkhozha S. Sharafiddinov, Theoretical Physics Division, Institute of Nuclear Physics,  
Uzbekistan  
Institute for Plasma Research, University of Maryland, USA  
Librarian, Fusion Energy Division, Oak Ridge National Laboratory, USA  
Librarian, Institute of Fusion Studies, University of Texas, USA  
Librarian, Magnetic Fusion Program, Lawrence Livermore National Laboratory, USA  
Library, General Atomics, USA  
Plasma Physics Group, Fusion Energy Research Program, University of California  
at San Diego, USA  
Plasma Physics Library, Columbia University, USA  
Alkesh Punjabi, Center for Fusion Research and Training, Hampton University, USA  
Dr. W.M. Stacey, Fusion Research Center, Georgia Institute of Technology, USA  
Dr. John Willis, U.S. Department of Energy, Office of Fusion Energy Sciences, USA  
Mr. Paul H. Wright, Indianapolis, Indiana, USA

The Princeton Plasma Physics Laboratory is operated  
by Princeton University under contract  
with the U.S. Department of Energy.

Information Services  
Princeton Plasma Physics Laboratory  
P.O. Box 451  
Princeton, NJ 08543

Phone: 609-243-2750  
Fax: 609-243-2751  
e-mail: [pppl\\_info@pppl.gov](mailto:pppl_info@pppl.gov)  
Internet Address: <http://www.pppl.gov>